

D

Output signal inspection

- Connect power transistor unit and ECCS C/U harness connector.
- Check power voltage between ECCS C/U terminal 1, 2, 3, 11, 12 & 13 and body earth.

When cranking:	Approx. 0.05V
When idling:	Approx. 0.05V
At 2500rpm:	Approx. 0.1V

